

[illegible]

PRINT DATE: 9/14/2026 9:18:31 AM

DRAWING TITLE
EXTERIOR BUILDING ELEVATIONS

DRAWN BY	RG	SHEET NO. A-6.10
CHECKED BY	CA	
APPROVED BY	TB	

FAUX EXTERIOR WOOD BEAM

- ## STAIN SAMPLES AND MOCK-UP

STAIN SAMPLES AND MOCK-UP

- ## STAINING AND INSTALLATION

STAINING AND INSTALLATION

1. Following approval of the completed mock-up, Painting Contractor shall pre-stain all cedar boards prior to installation, including faces, edges and end grain. Provide premium exterior penetrating semi-transparent stain specifically recommended for Western Red Cedar and suitable for exterior exposure. Apply in accordance with stain manufacturer's written requirements.
2. Painting Contractor shall provide Carpenter with the approved exterior stain for treatment of field-cut cedar.
3. Carpenter shall apply approved stain to all field-cut edges and end grain prior to installation and assembly. Allow field-applied stain to dry in accordance with stain manufacturer's requirements prior to final assembly.
4. Carpenter shall apply stain to freshly cut surfaces only. Protect pre-stained exposed faces from drips, runs, overruns or additional stain. Do not apply additional stain to pre-finished exposed faces. Immediately remove accidental stain from pre-finished surfaces in accordance with stain manufacturer's recommendations.
5. No raw or unfinished cedar shall be visible at completed joints. Staining of mating edges and end grain prior to assembly is intended to prevent unfinished wood from becoming visible due to normal future movement of the cedar.
6. Following installation, Painting Contractor shall fill and sand exposed fastener holes and perform final stain touch-up only as required to provide a uniform finished appearance consistent with the approved mock-up.
7. Do not apply additional stain to previously finished exposed surfaces unless required to achieve the approved appearance and permitted by the stain manufacturer. Avoid lap, marked areas, drips, runs or other variations caused by overlapping stain applications.
8. Do not apply a separate clear sealer, polyurethane or other film-forming clear coat unless specifically approved by Architect.
9. Completed beams shall be straight and true, with tight and consistently aligned joints, uniform finish and the overall appearance of solid exterior wood beams.

ELEVATION KEYNOTES	
NOTE NUMBER	NOTE TEXT
01	SOLDIER COURSE BR-01
02	EXTERIOR LIGHT FIXTURE RE: ELEC. DWGS
03	HARDIE BOARD FASCIA. COLOR TO MATCH STAINED RE: SCHEDULE
04	EXTERIOR BUILDING SIGNAGE RE: A-14.10
05	STRUCTURAL STEEL WRAPPED IN STAINED CEDAR
06	GUTTER AND DOWNSPOUT RE: SCHEDULE RE: 02/A-5.00
07	DECORATIVE NON-FUNCTIONAL LOUVER VENT
08	MT-01 CANOPY WITH CEDAR STAINED WOOD BRACKETS
09	PAINTED HOLLOW METAL DOOR

