



E/B/E PROJECT NUMBER: 26181.00

[illegible]

~~09/30/2025~~

P1.01



A. NO COPPER OR BRASS FITTINGS DOWNSTREAM OF BACKFLOW PREVENTER.

B. WATER FILTRATION BEFORE BACKFLOW PREVENTER.

- 1 NEW WATER HEATER SUSPENDED ABOVE ACCESSIBLE CEILING. COORDINATE WITH MEP IN THE AREA. REFER TO DETAILS.
- 2 EXISTING SINK TO BE REMOVED. CUT AND CAP WASTE AND WATER CONNECTIONS BACK TO POINT OF USE AS REQUIRED.
- 3 CONNECT NEW 1" COLD WATER TO EXISTING WATER ABOVE CEILING. VERIFY SIZE AND LOCATION PRIOR TO START OF WORK.
- 4 ROUTE COMMON 3/4" COLD WATER LINE FOR PLUMBING EQUIPMENT WITHIN COFFEE BAR.
- 5 CONNECT NEW 2" VENT TO EXISTING VENT RISER ABOVE CEILING. PROVIDE CAPPED TEE FOR FUTURE. VERIFY SIZE AND LOCATION PRIOR TO START OF WORK.
- 6 CONNECT NEW 3" WASTE TO EXISTING WASTE STACK. VERIFY SIZE AND LOCATION PRIOR TO START OF WORK.

EXISTING PLUMBING PIPING LOCATIONS SHOWN ON THIS DRAWING ARE APPROXIMATE.
FIELD VERIFICATION IS REQUIRED. LOCATIONS SHOWN ARE BASED UPON LIMITED SITE
SURVEY INFORMATION. COORDINATE FOR EXACT LOCATIONS OF NEW PLUMBING
EQUIPMENT FOR COFFEE BAR WITH ARCHITECT.

